



TOP SLAB LAYOUT OPTIONS



TERRE KLEEN - GENERAL NOTES:

THE TERRE KLEEN™ (US PATENT 6,676,832 B2) HYDRODYNAMIC SEPARATOR AS DESIGNED, MANUFACTURED AND TESTED BY TERRE HILL CONCRETE PRODUCTS, INC. IS THE ONLY PRODUCT OF ITS KIND AVAILABLE IN THE UNITED STATES. CONTACT: TERRE HILL STORMWATER SYSTEMS AT P.O. BOX 10, 485 WEAVERLAND VALLEY ROAD, TERRE HILL, PA 17381 (PHONE 1-800-242-1599) OR WWW.TERRERESPON.COM

CONCRETE: Fc = 5000 PSI @ 28 DAYS, WITH ASTM C-313 NO. 57 OR NO. 67 COARSE AGGREGATE

DEFORMED STEEL CONCREMS TO ASTM A615 GRADE 60, WELDED WIRE FABRIC CONCREMS TO ASTM A185 AND SHALL CONFORM TO ASTM A497

BRUSHED CONCRETE CS-1028 JOINT MATERIAL MANUFACTURED BY CONCRETE SEALANTS, INC. AND CONCREMS TO FEDERAL SPECIFICATION SS-5-270A. JOINT SEALANT MUST BE INSTALLED IN ACCORDANCE WITH CONCRETE SEALANTS, INC. RECOMMENDATIONS.

ANNUAL SPACE BETWEEN PIPE AND HOLE TO BE FILLED. BY OTHERS, WITH AN APPROVED NON-SHRINK GROUT OR CONCRETE AS SPECIFIED.

ALL PIPES TO BE CUT FLUSH WITH INSIDE WALL, AFTER GROUT HAS DRIED.

DEPT-N ANCHORS TO BE HILL 316 STAINLESS STEEL KMK BOLT II AS MANUFACTURED BY HILL CORP. UNI LIFT ANCHORS MANUFACTURED BY UNIVERSAL FORM CLAMP COMPANY, OR EQUAL, UNI LIFT ANCHORS TYPICAL FOR HANDLING.

MANHOLE FRAMES AND COVERS SUPPLIED BY TERRE HILL STORMWATER SYSTEMS. INSTALLATION AND GRADE ADJUST BY OTHERS. COVERS TO BE MARKED WITH TERRE KLEEN STORMWATER TREATMENT SYSTEM LOGO. INSTALLATION AND MAINTENANCE MUST BE IN ACCORDANCE WITH THE MANUFACTURERS WRITTEN INSTRUCTIONS AND COMPLY WITH LOCAL ORDINANCES AND NPDES PHASE II REGULATIONS.

- #### Terre Kleen T100 Performance, Design and Installation Specifications
- Terre Kleen is a HYDRODYNAMIC SEPARATOR consisting of prefinished, stacked inclined plates housed inside a precast structure. Terre Kleen removes pollutants by separating sediment and floatables such as oils, grease, trash and debris from stormwater. Terre Kleen features one or follows:
- capture & permanently retain 100 percent of feedable trash & debris of all flows
 - remove 90 percent of feedable sediment, silt, sand, and debris
 - permanently remove captured oil, grease and TPH
 - capable of removing silt and city size particles
 - All storm water flows shall enter the Terre Kleen unit, flows in excess of design flows, shall pass through the internal flow through duct to the effluent pipe without the use of an external bypass.
 - Stormwater and debris in the grit chamber are self cleaning settling surfaces
 - biogrowth prevention
 - Certified sediment, organic solids and other settled material in the primary and grit chambers are stored in a sump area containing not less than 99.0 Gals; entire sump area including settling surfaces and the treatment flow path, preventing re-suspension of material
 - Minimum volume of captured gross pollutant sump area is 99.0 Gals
 - Minimum gross oil storage capacity is 245 gallons
 - 18 inch manhole access for maintenance from grade by vacuum truck; with not less than 18 inch continuous access opening to bottom of sump area
 - 30\"/>

- #### Maintenance Procedures
- Quarterly inspection is recommended to record sediment, oil, and trash accumulation.
 - Cleaning is recommended when the sediment reaches 16 inches in depth in one or both sumps.
 - No confined space entry required. Terre Kleen design allows access from grade, to both chambers by vacuum hose for removal of 100% of all captured pollutants.
 - Air and water pressurized sludge dispersion manifold, under inclined plates
 - Removed material must be handled and disposed according to local, state, and federal regulations
- #### Terre Kleen Installation Specifications
- Terre Kleen inclined plate assembly shall arrive at the job site fully assembled inside precast concrete structure. Precast structure shall contain lifting points with Uni-Lifts, and be designed to be lifted by the structure. If required shall be included as shown on the drawings and grade adjusted to match final grade elevation by Contractor.
 - Contractor shall excavate, dewater and shore in accordance with project specifications, as provided by Engineer and OSHA regulations.
 - Sub-grade shall be established as shown on the Drawings. Underlying soil and sub-grade material shall have design loading of not less than 2000 pounds per square foot (psf). Precast components shall be placed on the compacted base (3% Proctor Density), elevation provided by Engineer and OSHA regulations.
 - Contractor shall place "CONSEAL" or equivalent water tight mastic material between each precast component.
 - Precast structure containing the Terre Kleen component shall be aligned horizontally and vertically plumb. Contractor must confirm that the entire Terre Kleen shall be level during and after completion of backfill. The structure, if required shall be included as shown on the drawings and grade adjusted to match final grade elevation by Contractor.
 - Connect and seal storm drain inlet and outlet pipes to Terre Kleen unit using non-shrink grout-fill material in accordance with project specifications.
 - BACKFILL SPECIFICATIONS: It is recommended that the stone sub-base be extended a minimum of one foot (1 ft) beyond the exterior face of the precast and compacted to 95% Proctor Density. Upon completion of the precast installation of 90% Proctor Density, or as specified by the Engineer, when tested by ASTM A1557. Backfill material may be a "minimal composition effort" material. Native material may be used if the material provides an allowable bearing pressure of 2000 pounds per square foot (psf) and compacts to 90% Proctor Density per ASTM A1557, if approved by the Engineer. In areas of vehicular use, the upper two feet (2 ft) of backfill shall be aggregate base, compacted to 95% Proctor Density (ASTM A1557).
 - Contractor shall remove all foreign material and debris including all sediment, oils, grease and debris from the inlet pipe, outlet pipe and Terre Kleen upon completion of installation.

Terre Kleen Model	Settling velocity diameter d ₅₀ Micron	Design ¹ Capacity flow loss d ₅₀ =50	Design ¹ Capacity flow loss d ₅₀ =110	Design ¹ Capacity flow loss d ₅₀ =150	Design ¹ Capacity flow loss d ₅₀ =200	Design ¹ Capacity flow loss d ₅₀ =250	Peak flow head loss	Peak ^{2,4} head loss	max pipe Dim.	Standard Storage	Standard ⁵ volume	Minimum pipe invert	Standard pipe bottom	
TK01	8 SFPI	0.17 cfs	< 0.50 ft	0.5 cfs	< 0.50 ft	1.0 cfs	< 0.50 ft	2.5 cfs	0.00 ft	18 in.	66 CF	192 Gallon	2.52 Ft	6.25 Ft
TK02	13 SFPI	0.27 cfs	< 0.50 ft	0.8 cfs	< 0.50 ft	1.6 cfs	< 0.50 ft	4.0 cfs	0.21 ft	18 in.	98 CF	123 Gallon	3.27 Ft	6.25 Ft
TK05	32 SFPI	0.4 cfs	< 0.50 ft	2.1 cfs	< 0.50 ft	3.9 cfs	< 0.50 ft	10.0 cfs	0.81 ft	18 in.	193 CF	238 Gallon	3.27 Ft	6.25 Ft
TK08	48 SFPI	0.5 cfs	< 0.50 ft	3.2 cfs	< 0.50 ft	5.4 cfs	< 0.50 ft	15.0 cfs	1.21 ft	18 in.	288 CF	354 Gallon	3.27 Ft	6.25 Ft
TK18	115 SFPI	1.5 cfs	0.10 ft	7.5 cfs	0.44 ft	13.9 cfs	0.87 ft	26.0 cfs	36.00 ft	48 in.	110 CF	203 Gallon	3.27 Ft	6.25 Ft
TK27	172 SFPI	2.3 cfs	0.11 ft	11.2 cfs	0.27 ft	20.8 cfs	0.38 ft	37.0 cfs	26.00 ft	42 in.	151 CF	285 Gallon	3.27 Ft	6.25 Ft
TK36	239 SFPI	3.1 cfs	0.13 ft	16.0 cfs	0.24 ft	27.8 cfs	0.17 ft	48.5 cfs	32.00 ft	42 in.	216 CF	327 Gallon	3.27 Ft	6.25 Ft
TK45	288 SFPI	3.9 cfs	0.13 ft	18.7 cfs	0.24 ft	34.9 cfs	0.17 ft	62.0 cfs	33.81 ft	60 in.	297 CF	389 Gallon	3.27 Ft	6.25 Ft
TK54	348 SFPI	4.7 cfs	0.16 ft	22.5 cfs	0.24 ft	41.9 cfs	0.24 ft	74.5 cfs	39.25 ft	72 in.	299 CF	482 Gallon	3.27 Ft	6.25 Ft

1. Design flow rates based on Weighted Removal according to NIDEP lab protocol and adjusted for a particle density 1400ps/cft and 60 degree Fahrenheit water temperature.
 2. Peak headloss is defined by the standard insert clearance and defines cost flow.
 3. Add 3" for grade adjust and frame and cover, otherwise cost into the lid.
 4. Excess design overflow through a screen is possible above insert.
 5. Special designs are available to increase these values.

Revision Δ 11-12-08
 Initial Release 9-16-08

TERRE KLEEN™ is a registered US Patent (US Patent 6,676,832 B2)

TERRE HILL STORMWATER SYSTEMS
 Improving Your World™

TERRE HILL, PA. (717)445-3100

TERRE KLEEN™ 09
 PRECAST WATER QUALITY CHAMBER

REVISIONS

JOB: WATER QUALITY CHAMBER

CONTR: _____

ENGR: _____

By: _____ DATE: _____

SHT. 1 OF 1